



DEPARTMENT OF PUBLIC WORKS
Maple Street Annex
725 Maple Street - PO Box 100
Hillsboro, Missouri 63050
(636)797-5340 – www.jeffcomo.org

Last Updated: **Tue Oct 8, 2024**

PUBLIC INFORMATION SHEET

- 1. Project Identification:** Laguna Palma Rd Bridge
STP-5403(697)
- 2. Resident Engineer:** Robert Russell
- 3. County Representative:** Robert Russell 636.797.5342
RRUSSELL@JEFFCOMO.ORG
- 4. County's Consultant:** ABNA
- 5. Council District(s):** 6
- 6. Approximate Date for Approved Final Plans:** Summer 2023
- 7. Additional Right-of-Way Required?:** Yes
- 8. Approximate Date of Right-of-Way Acquisition:** Fall 2022
- 9. Length of Road or Bridge Project:** 50 Feet
- 10. Existing Bridge Rating and Load Posting:** 40.5% 16 TON
- 11. Contract Amount:** \$1,092,909.00
- Low Bid?:** Yes
- Funding Source:** 80% Federal 20% Local
- 12. Contractor:** Gershenson Construction Co., Inc.
- 13. Contract Performance Period:** 12/31/2024 Completion Date
- 14. Estimated Construction Start Date:** Winter 2023
- 15. Estimated Construction Completion Date:** Winter 2024

16. Project Details:

Replacement of deficient structure on Laguna Palma Road at Boyd Branch Road. There will be roadwork to tie the bridge back into the roadway. The abutments and disturbed creek channel will be lined with heavy stone revetment. The bridge will include twelve-foot lanes, four-foot shoulders and a concrete barrier curb.



DEPARTMENT OF PUBLIC WORKS
Maple Street Annex
725 Maple Street - PO Box 100
Hillsboro, Missouri 63050
(636)797-5340 – www.jeffcomo.org

Last Updated: **Tue Oct 8, 2024**

PUBLIC INFORMATION SHEET

1. **Project Identification:** Mcgehan Road Bridge
STP-5403(698)
2. **Resident Engineer:** Robert Russell
3. **County Representative:** Robert Russell 636.797.5342
RRUSSELL@JEFFCOMO.ORG
4. **County's Consultant:** ABNA
5. **Council District(s):** 6
6. **Approximate Date for Approved Final Plans:** Summer 2023
7. **Additional Right-of-Way Required?:** Yes
8. **Approximate Date of Right-of-Way Acquisition:** Fall 2022
9. **Length of Road or Bridge Project:** 50 Feet
10. **Existing Bridge Rating and Load Posting:** 39.8% 13TONS
11. **Contract Amount:** \$796,311.00
Low Bid?: Yes
Funding Source: 80% Federal 20% Local
12. **Contractor:** Gershenson Construction Co., Inc.
13. **Contract Performance Period:** 12/31/2024 Completion Date
14. **Estimated Construction Start Date:** Winter 2023
15. **Estimated Construction Completion Date:** Winter 2024

16. Project Details:

Replacement of deficient structure with vertical alignment improvements. The abutments and disturbed creek channel will be lined with heavy stone revetment. The bridge will include twelve-foot lanes, four-foot shoulders and a concrete safety barrier curb.