



DEPARTMENT OF PUBLIC WORKS
Maple Street Annex
725 Maple Street - PO Box 100
Hillsboro, Missouri 63050
(636)797-5340 – www.jeffcomo.org

Last Updated:

Fri Jan 10, 2025



PUBLIC INFORMATION SHEET

- | | | |
|---|--|--------------------------------------|
| 1. Project Identification: | ST 0059 Project Redbird Phase 1 (Castle Acres) | |
| | River Cement Rd | |
| 2. Resident Engineer: | Lane Harness | |
| 3. County Representative: | Lane Harness | 636.797.5573
LHARNES@JEFFCOMO.ORG |
| 4. County's Consultant: | Horner and Shifrin | |
| 5. Council District(s): | 5 | |
| 6. Approximate Date for Approved Final Plans: | Winter | 2023 |
| 7. Additional Right-of-Way Required?: | No | |
| 8. Approximate Date of Right-of-Way Acquisition: | - | - |
| 9. Length of Road or Bridge Project: | ~2 | Miles |
| 10. Existing Bridge Rating and Load Posting: | N/A | |
| 11. Contract Amount: | \$1,775,841.90 | |
| Low Bid?: | Yes | |
| Funding Source: | 75% State | 25% Local |
| 12. Contractor: | Gershenson Construction Inc. | |
| 13. Contract Performance Period: | 12/30/24 | Completion Date |
| 14. Estimated Construction Start Date: | Summer | 2024 |
| 15. Estimated Construction Completion Date: | Spring | 2025 |
| 16. Project Details: | | |

The use of full depth reclamation (cement stabilized base) to rebuild Castle Acres Road and River Cement Road. Each road will also be base widened to a total width of 26 feet (11ft lanes 2 ft shoulders). All of the improvements will be capped with an asphalt overlay. There will be some earthwork to tie back into existing grade. We will also be widening and installing a new left turn lane from River Cement Road onto Castle Acres Road. Please see the website for additional information (see below). When construction begins anticipate daily lane closures.

For more information see Project Plans and Specifications at www.jeffcomo.org/.....