

---

## ADDENDUM FORM

---

Project Name: Mark Drive NID – Sanitary Sewer Extension

Project Number: 10030003

Project Sponsor: Jefferson County,  
Jefferson County Administration Building  
729 Maple Street  
Hillsboro MO 63050

Project Engineer: Trumpet Land Services LLC  
575 Rudder Rd., Suite 105  
Fenton, MO 63026  
Contact: Douglas S. Bjornstad P.E.

Addendum #: 01

Addendum Date: 11-01-11

THIS BID CLARIFICATION FORM SHALL BE A PART OF THE CONTRACT DOCUMENTS: IT SUPPLEMENTS AND MODIFIES THE BID DOCUMENTS (DATED 10-11-11)

**BID DOCUMENTS:**

1. Page 0030 – BID FORM 2 and Page 00460 Agreement Form 2; Bid Item 104 – 4" PVC Gravity Sewer, change the Unit from Cu. Yd. to Lin. Ft. (4" PVC Gravity Sewer 2625 Lin. Ft.)
2. Page 0030 – BID FORM 2 and Page 00460 Agreement Form 2, Service Connection, See Plan Sheet 8 of 8 Construction Standards for Typical Service Connection Details.
3. Page 0030 – BID FORM 2 and Page 00460 Agreement Form 2; Bid Item 115 and 116 – Clarification: The home owner will make the septic tank accessible. That is, if the septic tank is inaccessible due to a permanent construction (i.e. porch, garage) then the home owner will be responsible for making the septic tank accessible.
4. Page 0030 – BID FORM 2 and Page 00460 Agreement Form 2; Bid Item 120 – This bid item includes all construction, material, labor and incidentals for construction the street crossing as shown in the Detail for Open Cutting of Asphalt Road, Page 2 of 8, of the project plans
5. Page 0030 – BID FORM 3; 5. Substitute Calendar Day for Working Days. "Bidder agrees that the work will be completed within 150 Calendar Days."

# Trumpet Land Services LLC

575 Rudder Rd; Suite 105, Fenton, MO 63026

Phone (636) 326-5551 Fax (636) 326-5570



6. 0030 – Bid Form 2 and Page 00460 Agreement Form 2. Item 126, Contractor Construction Staking. and Page 00500- General Conditions 3; Part 9, Survey: Clarification, Contractor is responsible for all construction staking. Engineer will make available coordinate geometry of control points and sewer main alignment for the contractor.

## **DRAWINGS:**

1. Page 2 of 8; Erosion Control, 1), Substitute the word Contractor for the word Owner. I.e. The Contractor assumes complete responsibility for installation/maintenance of project erosion control measures....,
2. Page 6 of 8; laterals for Lot 20 and 21 Short Dr, Lots 10-10a Bow Dr. will be connected to the sanitary sewer. Laterals for lots 19 Bow Drive and Lots 9 and 11 Short Drive will be will extend to 10 past the creek and capped. The capped will be marked with a pressure treated wood marker that extends two feet above ground. 6" Ductile Iron pipe shall be used for the creek crossings.
3. Page 7 of 8; Restrained Joint piping shall be used for any pipe Installed at 20% +/-.
4. Page 8 of 8; Service Connections refer to the installation of the Elder Valve and Riser pipe. Coordinate location of service connection with Sewer District.

## **SPECIFICATIONS**

None

## **END OF ADDENDUM**