

ADDENDUM 1

BID FOR: Annex Building Parking Lot Improvements Project PW-15B003

1. Plan Sheet C-001, Site Grading notes, Notes # 18, 23 and 24 shall not apply. Jefferson County will be responsible for all geotechnical testing.
2. "No Parking" paint shall be included with the striping amounts.
3. Geotextile fabric under aggregate shall meet AASHTO M-288 Separation Class 2 non-woven Geotextile.
4. Optional trench drain shall include installation. A short length of 8" PVC pipe and break in connection to an existing curb inlet will be necessary.